



Lee County Mosquito Control District Chiller Upgrade

From: ADG Architecture llc

Project Number: 2023-J-108

Date: 03.01.2024

RE: Addendum #4

The documents included in this revision shall become a part of the Contract Documents and modify the original Permit/Bid documents dated 08-11-2023.

Here is a brief description of the changes in this addendum:

QUESTIONS ISSUED BY PROPOSERS:

Questions from proposers are shown in italics, answers by A/E or Lee County Mosquito Control District staff shown in bold.

1. *Question: Can you provide specifications on the underground valve box (sizes)?*

Answer: Per addendum #4 documents, we are tapping existing chilled water lines and providing new valves above grade at the existing building (Building A). No new valve boxes are required.

2. *Question: Can you provide details and specifications for the digging, refill and paving of the parking lot/asphalt for the new chiller line branches to the existing building?*

Answer: Refill & paving to match existing.

3. *Question: Can you provide keynote 8 for page M001 as to the connection to the existing building?*

Answer: Keynote 8 has been modified based on scope of work required.

4. *Question: Is the chiller owner provided?*

Answer: Yes, the chiller has already been purchased by the Lee County Mosquito Control District.



Lee County Mosquito Control District Chiller Upgrade

5. *Question: Regarding the underground pipe, do you want PVC or black HDPE jacketing on the pipe?*

Answer: I will specify schedule 40 black steel piping pre-insulated with HDPE jacket.

DRAWINGS

ARCHITECTURAL

-- -- TITLE SHEET – Re-Issued

- Sheet index schedules added addendum #4 column with all revised sheets noted.

MECHANICAL

M100 – CHILLER PLAN – Re-Issued

- Removed valve box from mechanical plan.
- Specified location of new chilled water supply and return piping stub up.
- Specified new piping to be pre-insulated schedule 40 black steel with insulation and HDPE jacket.

SPECIFICATIONS

No changes to specifications.

END OF ADDENDUM #4